*RA10

DRAFT **CONTRACT CHANGE ORDER**

Date: November 4, 2008

To: Mr. Hassan Bitar
Granite Construction Company
715 Comstock Street
Santa Clara, CA 95054-3403

Project: Singley Area Rehabilitation, Phase V, Project No. 8193

Contract Change Order No. 6
Description: Eliminate Pavement Dips on Milpitas Blvd.
Ref: CP 8194-7-4237
City Council Approval: 11/18/08

You are hereby authorized to proceed with the following work in connection with the subject project:
Furnish all labor, materials and equipment to eliminate the two dips on the number one southbound lane of Milpitas Blvd. between Hanson Ct. and Abel St./Jacklin Rd.:

1. Abandon southern inlet and 12" RCP pipe connecting to the northern inlet. Fill the abandoned inlet and pipe with a two sacks slurry mix
2. Replace top of southern inlet with vertical concrete curb
3. Raise northern inlet 3" and save in place
4. Grind asphalt concrete for a total of 175' long and 10' wide. The final AC lift shall be 1.5" minimum
5. Pave surface to drain
6. Traffic control
7. Mobilization

TOTAL: $ 68,000.00

INCREASE IN CONTRACT TIME: none

No claims for additional compensation or damages for delay under any theory whatsoever, submitted by the contractor or any subcontractor, will be allowed by the City for any delay arising from, or associated with this change order. The extension of the time for completion and the compensation specified in this change order shall be the contractor's sole remedy.

This change order constitutes full and complete compensation for all labor, equipment, materials, overhead, extended overhead and profit required to perform the changes described above in accordance with the applicable provisions of the contract documents. This change order is not effective until approved by owner.

Accepted By:_____Date: _____
Granite Construction Company

City Project Manager: _____ City Project Inspector: _____
Initial initial

City Approval:_____Date:_____
City Engineer