CITY OF MILPITAS
ENGINEERING DIVISION
Bid Summary

25

JOB TITLE: Sewer Deficiency & Structural Correction Program - Project No. 6073
6073 Sewer Deficiency and Structural Correction Program- OPEN CUT
Bid Date: July 13, 2006

				Engineers Estimate		Pacific Underground San Jose, CA		Fermin Sierra Construction Union City, CA		JMB Construction So San Francisco, CA	
ITEM	DESCRIPTION	Qty	Unit	Unit Cost	Extension	Unit Cost	Extension	Unit Cost	Extension	Unit Cost	Extension
1	Mobilization	1	LS	$60,000	$60,000	$40,000	$40,000	$60,000	$60,000	$72,732	$72,732
2	Traffic Control	1	LS	$50,000	$50,000	$20,350	$20,350	$30,000	$30,000	$63,700	$63,700
3	Trench Safety	1	LS	$40,000	$40,000	$15,000	$15,000	$30,000	$30,000	$36,468	$36,468
4	Stormwater Pollution Prevention Plan (SWPPP)	1	LS	$20,000	$20,000	$6,000	$6,000	$30,000	$30,000	$30,000	$30,000
5	Pothole for existing utilities	1	LS	$39,180	$39,180	$5,000	$5,000	$30,000	$30,000	$15,000	$15,000
6	Construct utility supports for rigid utilities	18	EA	$1,500	$27,000	$300	$5,400	$1,650	$29,700	$1,020	$18,360
7	Site SE1 - 380 Monmouth to Monmouth at Edsel Open cut installation, remove 6" VCP pipe, new 8" PVC pipe.	329	LF	$210	$69,090	$190	$62,510	$120	$39,480	$180	$59,220
8	Replace active service lateral connection	11	EA	$600	$6,600	$300	$3,300	$1,000	$11,000	$496	$5,456
9	Rechannel manhole	2	EA	$1,500	$3,000	$1,000	$2,000	$2,000	$4,000	$1,040	$2,080
10	Root removal from service lateral	4	EA	$700	$2,800	$500	$2,000	$300	$1,200	$601	$2,404
11	Site SE6 - 1425 Saturn Ct to End of Court Open cut installation, remove 6" VCP, new 8" PVC pipe.	300	LF	$210	$63,000	$185	$55,500	$120	$36,000	$181	$54,300
12	Replace active service lateral connection	10	EA	$600	$6,000	$300	$3,000	$1,000	$10,000	$920	$9,200
13	New manhole	1	EA	$8,000	$8,000	$4,600	$4,600	$10,500	$10,500	$6,630	$6,630
14	Root removal from service lateral	14	EA	$700	$9,800	$500	$7,000	$300	$4,200	$601	$8,414
15	Rechannel manhole	1	EA	$1,500	$1,500	$1,000	$1,000	$2,000	$2,000	$1,040	$1,040
16	Site SE9 - Carnegie at Edsel to Freeland Open cut installation remove 8" VCP, new 8" PVC pipe.	500	LF	$210	$105,000	$218	$109,000	$150	$75,000	$180	$90,000
17	Replace active service lateral connection	17	EA	$600	$10,200	$300	$5,100	$1,000	$17,000	$496	$8,432
18	Root removal from service lateral	17	EA	$700	$11,900	$500	$8,500	$300	$5,100	$601	$10,217
19	Site N1 - 1665 Cortez to Coelho at Cortez Open cut installation remove 6" VCP, new 6" VCP pipe	40	LF	$350	$14,000	$300	$12,000	$400	$16,000	$185	$7,400
20	Site N2 - Dixon at Conway to Hetch Hetchy Open cut installation remove 8" VCP, new 8" VCP pipe.	40	LF	$500	$20,000	$500	$20,000	$380	$15,200	$185	$7,400
21	Site SE2 - Roswell Dr Adjust manhole rim elevation	6	EA	$700	$4,200	$1,700	$10,200	$1,500	$9,000	$1,900	$11,400
22	Site W1 - Spence at Whittier to Spence at Casper Open cut installation remove 8" VCP, new 8"PVC pipe.	424	LF	$230	$97,520	$200	$84,800	$150	$63,600	$182	$77,168
23	Replace active service lateral connection	13	EA	$600	$7,800	$300	$3,900	$1,200	$15,600	$755	$9,815
24	Site W6 - Norwich at Barker to Casper Open cut installation remove 10" VCP, new 10" PVC	263	LF	$370	$97,310	$230	$60,490	$240	$63,120	$196	$51,548
25	Replace active service lateral connection	4	EA	$600	$2,400	$300	$1,200	$1,850	$7,400	$576	$2,304
26	Site W7 - Norwich at Barker to 212 Barker Remove 8" VCP, install new 8" PVC pipe.	338	LF	$350	$118,300	$220	$74,360	$200	$67,600	$182	$61,516
27	Replace active service lateral connection	9	EA	$600	$5,400	$300	$2,700	$1,500	$13,500	$795	$7,155
					$900,000		$624,910		$696,200		$729,359
	Total						Apparent Low Bidder				

ESmith

7/13/2006