
CITY OF MILPITAS MIDTOWN NORTH MAIN STREET STREETSCAPE IMPROVEMENT PROJECT

PHASE ONE - IMPROVEMENT PLANS PROJECT NO. 8165 - DECEMBER 2006



SHEET INDEX DESCRIPTION

C-0.01 C-0.02

DEMOLITION PLAN - N. MAIN ST. C-2.01 PLAN AND PROFILE SHEET N. MAIN ST. - 9+31.14 TO 15+50 C-3.01 UTILITY PLAN AND PROFILE SHEET N. MAIN ST. - 9+31.14 TO 15+50 C-4.01 THRU C-4.04 CIVIL DETAILS EROSION CONTROL PLAN - N. MAIN ST. C-5.01 EROSION CONTROL DETAILS C-6.01 TRAFFIC SIGNAL TITLE SHEET/NOTES AND DETAILS C-7.01 C-7.02 C-7.03 C-7.04 N. MAIN ST. MID BLOCK CROSSWALK CONSTRUCTION STAGING PLAN N. MAIN ST. C-7.05 C-8.01 CONSTRUCTION STAGING PLAN N. MAIN ST. C-8.02 LANDSCAPING LANDSCAPE LAYOUT PLAN LANDSCAPE PLANTING PLAN LANDSCAPE IRRIGATION PLAN IRRIGATION NOTES AND LEGEND L-3.3 L-4.1 THRU L-4.2 IRRIGATION DETAILS
LANDSCAPE CONSTRUCTION DETAILS STREET LIGHTING E=1.01 STREET LIGHTING PLAN = N. MAIN ST. E=2.01 THRU E=2.03 STREET LIGHTING DETAILS

COVER SHEET & GENERAL CIVIL NOTES KEY MAP AND LEGEND

- NO COMPENSATION WILL BE ALLOWED FOR ANY ADJUSTMENT WHICH MAY BE PERFORMED BY THE OWNER OF THE FACILITIES. CONTRACTOR COORDINATE WITH UTILITY COMPANIES TO HAVE THEIR STRUCTURES ADJUSTED TO GRADE OR TO GRITAN WRITTEN PERMISSION FROM UTILITY COMPANIES TO ADJUST THEIR STRUCTURES TO GRADE FOR THEM.
- 11, UTILITY REPAIR: CONTRACTOR SHALL REPAIR ANY DAMAGE OR INTERRUPTION OF UTILITIES, WATER LINES OR IRRIGATION SYSTEMS IMMEDIATELY . TOILET FACILITIES: CONTRACTOR SHALL PROMDE PORTABLE SANITARY FACILITIES ADEQUATE FOR ALL WORKERS. THE TYPE OF TOILETS USED THER LOCATIONS AND MAINTENANCE SHALL BE IN COMPLIANCE WITH CAL/OSHA. HAND WASHING FACILITIES SHALL BE PROMDED NEARBY THE TOILET FACILITIES.
- 14. CONTRACTOR SHALL COMPLY WITH THE RULES AND REGULATIONS OF THE STATE CONSTRUCTION SAFETY ORDERS AND CAL/OSHA.
- WHEN HAULING ANY EARTH, SAND, GRAVEL, STONE, DEBRIS, PAPER, OR ANY OTHER SUBSTANCE OVER ANY PUBLIC STREET, ALLEY OR PUBLIC PLACE, THE CONTACTOR SHALL NOT ALLOW MATERIAL TO BLOW OR SPILL OVER AND UPON SAID PUBLIC, ADJACENT OR PRIVATE PROPERTY.
- 17. ALL TRENCH BACKFILL SHALL BE COMPACTED IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
- 18. ALL EXISTING IRRIGATION, LANDSCAPE MATERIALS, PAVEMENT DELINEATION, CURB AND GUTTER AND OTHER IMPROVEMENTS, THAT ARE NOT TO BE REMOVED BUT ARE DAMAGED DURING CONSTRUCTION, SHALL BE REPLACED OR RESTORED TO EXISTING CONDITION AT NO ADDITIONAL EXPENSE TO THE CITY.
- 20. BEFORE START OF WORK, CONTRACTOR SHALL SUBMIT A STORM WATER POLLUTION PREVENTION PLAN (SWPPP) TO CONTROL WATER POLLUTION DURING CONSTRUCTION OF THE PROJECT.
- 21. CONTRACTOR TO ENSURE ACCESS IS MAINTAINED TO ALL PRIVATE PROPERTY DURING CONSTRUCTION







Record Drawings		Submittal Log			Revisions			
	Num.	Description	Date	Num.	Description	Engr. Aprv.	Date	
	1	30% CD SUBMITTAL	10/11/05					
Project Engineer: Date:	2	65% CD SUBMITTAL	2/06/06					
	3	95% CD SUBMITTAL	5/12/06					
	4	100% CD SUBMITTAL	8/22/06					
Designer Date:	- 5	BID SET SUBMITTAL	12/20/06					
Public Works Inspector: Date:	Drawn	By: MCW						
Public Improvements Initially Accepted by	Check	Checked By: <u>MWB</u>						
the City Council on	ned By: MWB							



	CITY OF MILPITAS	PROJECT NO. 8165	
1	MIDTOWN NORTH MAIN STREET IMPROVEMENTS	BKF JOB NO.	
, I		20056022-10	
Μ	COVER SHEET & GENERAL CIVIL NOTES	E.P. NO.	
М	DESCRIPTIONS FOR GROUND BY		
9	RECOMMENDED FOR BIDDING BY: DATE:	SCALE: AS SHOWN	
	APPROVED FOR BIDDING BY: DATE:	C-0.01	
		C-0.01	